

**NILESH G. BHAGAT**

A.I.I.A., B.E. (Civil), A.M.I.E.

H. No. 864, "Geet Govind", A/P. Katta, Taluka-Malvan, Dist: Sindhudurg

09833472133 nileshgbhagat@gmail.com

Tender for furnishing work for Oriental Insurance Co. Ltd., Sanvordem Branch

No	Description	Qty	Unit	Rate	Amount
<b>A</b>	<b>FURNITURE WORK</b>				
1	<b>Gypsum Board False Ceiling :</b> Providing & Fixing ½" thk. Gypsum board false ceiling (Saint Gobain make) at 7'-6" from finished floor with galvanized 22/24 GI frame complete, with necessary offset, cutouts, including applying a coat of putty in the required manner & two coats of acrylic emulsion paint as per the shade approved.(ICI /Nerolac / Asian)	500	Sft.		
	Rate in words				
2	<b>Armstrong Tile Ceiling :</b> Providing & Fixing tile board false ceiling (Saint Gobain / Armstrong) as per the standard specifications at 8'-0" from finished floor complete, with necessary offset, cutouts, as per the standard manufacturer's specifications complete.	700	Sft.		
	Rate in words				
3	<b>Main Door for Branch :</b> Providing & fixing anodised aluminium frame 110mmx45mm styles and top with 135mm x 45mm and Bottom 150mmx 35mm with 6mm thk <b>Clear Glass Saint Gobain make panel</b> shutter (single leaf) with floor spring heavy duty (Magnum/Hyper/Everite) as per requirement and frosted film as per the design, handles "H" (30mm dia & 1000mm long) Kich/Magnum( Matt finished), locking arrangement at top and bottom, Push pull Plate 150mmx150mm as approved complete.	21	Sft.		
	Rate in words				
4	<b>Main Door side openings of the Branch :</b> Providing & fixing anodised aluminium openable shutters with 6mm thk glass embedded within the frame with necessary accessories like hinges, handles complete as directed. (Size 4'-0" x 1-0" - 2 nos)	10	Sft		
	Rate in words				
	<b>WOODEN PARTITION:</b>				
	General Specification: Making and fixing wooden partition made out 1-1/2"x2" Aluminium sections both ways vertically and horizontally 24" c/c apart and finished with 6mm marine ply (Sonear/Archid/Green make) and finished with lamination (1mm thk) as per pattern and design, french polished or zinc oxide polish wherever necessary as directed complete. The Al frame support shall be fixed to structural ceiling in a proper manner at interval of about 3'-0" apart. Frame shall be fixed with wooden plugs into the wall and flat screws driven into the wooden plug/to ceiling/ flooring/ walls. etc all fittings complete.The partition shall include 35mm thk flush door with laminate on both sides with all fittings including door closer, brass hinges, door locks, handles, stoppers, etc complete. Door opening edges ( viz. Jambs/cills) shall be provided with White Beach wood lipping with polish/paint finished as per the standard specifications of the Bank. (Note: The wooden partition area below false ceiling only will be considered for payment )				
5	<b>Full Ht. Fully Glazed Partition: (Manager's Cabin)</b> Making & Fixing fully glazed wooden (TW) partition as per design and profile with 12mm thk. clear float <b>glass (Saint Gobain make)</b> with etching/ frosted film as per the pattern/design approved by the architect. The glass partition shall held with top and bottom of runner made with 1-1/2"x2" Al sections and finished with ply both way laminated finished. Partition shall be provided with a openable shutters with ½" thk. glass <b>clear glass (2 Nos)</b> held in top and bottom rails 7"x 2" thk. & Styles 3 1/2" x2" polished complete with decorative SS NEKI / Magnum make (25mm dia x L 900mm main branch manager's cabin ,floor spring (Hyper/ Everite) with all accessories like ss plate cutting in the flooring for fixing floor machine, locking arrangement at top/bottom rail including complete as directed by the Architect.	200	Sft.		
	Rate in words				
6	<b>Full Ht. Both side laminated Partition: ( Store room)</b> As specified for general partition work but with 1mm thk. Laminate to the fixed partition and 6mm clear float glass 22"x36" (Saint Gobain make) for flush door as per the standard specification complete. Full Ht. Both side	130	Sft.		
	Rate in words				
7	<b>Cash Partition</b> with 12 mm thk clear glass as specified above but with 5'-6" ht. with 12mm thk clear glass (Saint Gobain make) as per the standard drawing finished complete.Cash Partition with 12 mm thk clear glass as specified above but with 5'-6" ht. with 12mm thk clear glass (Saint Gobain	130	Sft.		
	Rate in words				

8	<b>Low Ht Partition:</b> As specified above but with 4'-0" ht. with 12mm thk clear glass (Saint Gobain make) as per the instructions. The wooden partition shall be upto 3'-0" and 1'-0" glazed above. The glazed portion shall be provided with 1/2" thk. frosted film as directed. <b>Low Ht Partition:</b> As specified above but with 4'-0" ht. with 12mm thk clear glass (Saint Gobain make) as	125	Sft.		
	Rate in words				
	<b>Counter:</b> P/F counter made out of 19/12/6mm thk. marine ply (Archid/Green) as per the design/profile as specified. The writing desk made with 19mm+6mm thick marine ply top with half round white beach moulding (25mmx19mm) on edges lacquer finished including a cupboard unit consisting of 3 drawers equally placed with sliding telescopic channels (EBCO) along with fittings such as brass hinges, 'C' type handles, multipurpose locks Godrej /Dorset/Magnum all hardware and cable manager at the top working desk. The entire exposed surface / edges of the cupboard shall be provided with lamination. Front apron shall be finished as directed including glass 12mm thick clear glass on the counter top as directed. The counter shall include 19 mm thick ply as a shelf for CPU and footrest 3"x4" in salwood polish finished complete.				
9	<b>Low Ht.Counter :</b> As specified above (2'-6"ht ) for working desk as per the standard drawing finished complete. <b>Low Ht.Counter :</b> As specified above (2'-	18	Rft.		
	Rate in words				
10	<b>Cash Counter: ( As per standard design )</b> As specified above but height shall be 3'-10" high. The counter top shall be provided partly with 1/2" thk. Clear glass Saint Gobain make (6" wide) on side and 12" in the centre as per the profile and design. The drawer unit shall be provided with 3 nos. (7"/ 7"/ 9") compartments, Dorset /Godrej multipurpose locks, handles laquered finished fittings polishing complete as directed. <b>Cash Counter: ( As per standard design )</b>	5	Rft.		
	Rate in words				
	<b>WORK STATIONS : (Manager/ Staff, etc)</b>				
	Making & supplying wooden working desk as per item counter as per the instructions complete. The working desk shall be made out of 19mm/12/6mm thk marine ply (Sonear/Archid/Green). Edge of the top shall be finished with Beach Moulding with smooth and clear polish. All exposed surface shall be finished with lamination as per pattern/shade and the top shall be laminated finished as approved by the Company/architect.				
11	<b>Manager's Table: Size - 6'-0" X 3'-0" X 2'-6"H</b> Making & supplying Manager's table made out of 3/4" +6mm thk marine ply (Archid/Green) as per the profile and design. All exposed surface shall be laminated. The table shall be provided with beach wood moulding 19mmx25mm clear polished to all edges of the furniture complete with fittings and fixtures like handles, drawer locks (Godrej/Dorset make) etc. finished complete as per the standard specifications. <b>Manager's Table: Size - 6'-0" X 3'-0" X 2'-6"H</b>	1	No.		
	Rate in words				
12	<b>Officer's Table: Size - 5'-0" X 2'-6" X 2'-6"H</b> Same as above <b>Officer's Table: Size - 5'-0" X 2'-6" X 2'-6"H</b>	2	Nos		
	Rate in words				
13	<b>Electric cabinet :</b> Making and fixing wooden cabinet 9" deep wooden marine ply (Archid/ Green) for electric switches, etc. Sides front and Shutters shall be made out of 19mm the FRMP (Fire retardant Marine Ply) with polish inside and laminated finished externally & with collapsible open able hinges, aluminium ac grill 45 degree louvers, fire retardant paint from inside complete as specified. <b>Electric cabinet :</b> Making and fixing wooden cabinet 9"	25	Sft.		
	Rate in words				
14	<b>Paneling to column and door jambs :</b> Making wooden panelling made out with 8 mm thk marine ply (Archid/ Green) with 1mm thk. laminate finished as per approved shade & design complete as directed. <b>Paneling to column and door jambs :</b> Making wooden panelling made out with 8 mm thk marine ply	175	Sft		
	Rate in words				
15	<b>Wooden teapoy with glass top :</b> Supplying and laying wooden teapoy with tempered glass top 10mm thk. (top size 18" x 30" and shelf size 13"x26") having machine polished edges. The top shall be placed on wooden frame of 3" x1" laminated finished and with castors complete as directed. <b>Wooden teapoy with glass top :</b> Supplying and laying wooden teapoy with tempered	1	Nos		
	Rate in words				
16	<b>Wooden dining table with 4 chairs:</b> Providing and fixing wooden dining table having table top 3'-0" x 3'-0" with 4 wooden chairs for dining complete set as directed. <b>Wooden dining table with 4 chairs:</b> Providing and fixing	1	Set		
	Rate in words				
17	<b>Acrylic Emulsion Paint:</b> Scrapping down existing paint lime wash, etc. from surface and applying coats of putty in the required manner & 3 coats of plastic paint complete as per the shade approved.(Asian / Nerolac)	2500	Sft		
	Rate in words				

18	<b>Oil Paint to MS. Grills &amp; Windows / wooden doors shutters etc. Providing and fixing oil paint for door frames, shutters and ms grill including a coat of red-oxide for grill etc. as per the specification.</b>	500	Sft		
	Rate in words				
19	<b>Venetian blinds on windows:</b> P/F venetian blinds (Vista make) as per the specifications in ivory colour complete as directed.	150	Sft		
	Rate in words				
20	<b>Wooden storage:</b> P/F wooden storage 18" deep upto 8'-0" ht. made up of 18mm thk. Marine ply (Archid/ Green) and blockboard for shutters. The back ply shall be 6mm thk. And intermediate 18mm thk. Shelves shall be provided with tw lipping in the front as per the instructions of the branch. the shutters, front fascia and sides of the storage unit shall be finished with 1mm thk. laminate and internal surface shall be finished with polish/oil paint (white colour) complete as directed. The storage unit shall have dead locks (Godrej/Dorset), handles (Kich/ Dorset make), magnetic ball catch (Hettich/Dorset), door stoppers (Hettich/ Dorset), etc. including all hardware complete	225	Sft		
	Rate in words				
21	<b>Same as above but low ht storage 3'-0" ht.</b>	80	Sft		
	Rate in words				
22	<b>Shifting the safe as directed by the Company :</b> Shifting the existing safe to the place suggested by the Company and as shown in the plan with necessary labour etc.including all charges complete.Shifting the safe as	1	Job		
	Rate in words				
	<b>TOTAL AMOUNT FOR FURNITURE WORK Rs.</b>				
<b>B</b>	<b>CIVIL WORK</b>				
1	<b>Vitrified tile flooring:</b> P/F vitrified tiles <b>HR Johnson</b> 605mmx605mm Ivory as per the standard specification over the existing tiles by roughening the existing floor complete and using CM with Roffe as per he maufacturer's specification complete as specified including 4" skirting as directed. The work shall include laying of POP over the newly laid tiles to avoid scratches and due care shall be taken to ensure finished work. ( Basic cost of the tile shall be between Rs. 55/- to Rs. 60/- per sft )Vitrified tile flooring: P/F vitrified tiles <b>HR Johnson</b> 605mmx605mm Ivory as per the standard specification over	1200	Sft		
	Rate in words				
2	<b>Ceramic tile flooring in toilet block:</b> P/F ceramic tiles 300mmx300mm Kajaria/ HR Johnson as per the standard specifications over the new waterproofing done complete and using CM with Roffe as per he manufacturer's specification complete as directed. Ceramic tile flooring in toilet block: P/F ceramic tiles 300mmx300mm Kajaria/ HR Johnson as per the	65	Sft		
	Rate in words				
3	<b>Waterproofing:</b> Providing and fixing waterproofing using Roff / Araldite as per the standard specifications complete as directed.Waterproofing: Providing	100	Sft		
	Rate in words				
4	<b>Glazed tile dado:</b> P/F glazed tile 200mmx300mm Kajaria/ HR Johnson as per the standard specifications upto 7'-0" ht. over the new plastering (CM 1:4) done complete as directed. ( Basic cost of the tile shall be between Rs. 40/- to Rs.45/-)Glazed tile dado: P/F glazed tile 200mmx300mm Kajaria/ HR	350	Sft		
	Rate in words				
5	<b>Granite jambs and sills:</b> Providing and fixing 18mm thk. Average granite Jet black in double patti on CM 1:4 fixed in plumb for toilet block door frames as directed complete. (Basic cost of the granite is Rs.160/- to Rs.175/- per sft)Granite jambs and sills: Providing and fixing 18mm thk. Average	60	Rft.		
	Rate in words				
6	<b>EWC fitting:</b> Providing and fixing European water closet with seat cover (Hindustan / Parryware) white colour with flushing tank including necessary trap complete as directed.	1	No		
	Rate in words				
7	<b>IWC fitting:</b> Providing and fixing Indian water closet (Hindustan / Parryware) white colour with flushing tank including necessary trap complete as directed.	1	No		
	Rate in words				
8	<b>Wall mounted Wash basin :</b> Providing and fixing wash basin (Hindustan / Parryware) Size 24" x 14" white colour including necessary accessories like pillar cock, bottle trap, flexible pipe etc. complete as directed.	2	Nos		
	Rate in words				
9	<b>Plumbing Work and ancillary fixtures:</b> Providing and fixing CPVC pipes Tan coloured 1/2", 3/4", 1" including elbows, unions, tee, sockets etc, solvent cement (Prince make) and fittings like ( Jaguar make) bib cocks (2 nos) , angle cock ( 2 nos) stop cocks (2 nos) etc. complete as directed and required.	1	Job		
	Rate in words				

10	<b>Ventilators for toilet blocks :</b> Providing and fixing Aluminium ventilator louvers with 4mm baja glass. Provision for exhaust fan fixing shall be made using 18mm thk ply of size 12"x12" and frame using wire mesh shall be fixed to the ventilator to restrict the entry of insects complete as directed.	2	Nos		
	Rate in words				
11	<b>Syntex doors for toilets:</b> Providing and fixing Syntex doors as per the standard specifications and as per the size required as directed. (Size 7'-0" x 2'-6")	2	Nos		
	Rate in words				
12	<b>Rolling shutter:</b> Providing and fixing new rolling shutter as per the standard specifications with a coat of red oxide and two coats of oil paint complete as directed. ( Min. 50 Sft)	50	Sft		
	Rate in words				
<b>TOTAL AMOUNT FOR CIVIL WORK Rs.</b>					
<b>C CHAIRS</b>					
1	<b>Manager Chair:</b> P/S manager chair (high back) as per the fabric colour and shade approved by the Company. Manager Chair: P/S manager chair (high	1	No		
	Rate in words				
2	<b>Officer chair:</b> As above but without high back and with handles Officer chair:	7	Nos		
	Rate in words				
3	<b>Visitor chair:</b> Same as item 2. above but without handles Visitor chair: Same	7	Nos		
	Rate in words				
4	<b>3 seater sofa:</b> P/S 3 seater sofa having HD foam and upholstery with handles. (The basic cost of the fabric shall be Rs.450/- per mt.) The sofa shall be fabricated as per the design approved by the Architect/ Company. 3 seater sofa: P/S 3 seater sofa having HD foam and upholstery with handles. (The	1	No		
	Rate in words				
<b>TOTAL AMOUNT FOR CIVIL WORK Rs.</b>					
<b>D ELECTRICAL WORK</b>					
1	<b>Main Panel board</b>	1	No		
	SITC of 100A 4 pole MCCB with 25KA breaking capacity in sheet metal enclosure (L&T / Siemens) with 63A Cu bus bar having CT connections, - Outgoing 63A TPN isolater -3 nos, 32A/16A/10A SPMCB-12 nos with all accessories like digital voltmeter/ Ammeter and RYB indicators complete as required.				
	Rate in words				
2	<b>Lighting DB</b>	1	No		
	SITC of 4way three phase DB ( Legrand / Siemens) of Incommer-63A TPN MCB -1no. & Outgoing -10/16A/20A SPMCB -12 nos				
	Rate in words				
3	<b>UPS DB</b>	1	No		
	SITC of 12way DB (Legrand/Siemens) of Incommer-40A DP MCB -1no. & Outgoing -10/16A SPMCB -10 nos				
	Rate in words				
4	<b>UPS Input</b>	2	No		
	SITC Incommer-63A 2 pole MCB in ms enclosure box ( Legrand / Siemens )				
	Rate in words				
5	<b>UPS Output</b>	1	No		
	SITC 40A DP MCB in ms enclosure box ( Legrand / Siemens )				
	Rate in words				
	SITC of LT cable Polycab make rated for 600/1100V AC as per IS with accessories and terminations like brass glands (Dowells / Braco), Cu lugs etc.				
6	<b>4core x25sqmm Al armoured cable</b> from pole to MDB with all connections complete. <b>4core x25sqmm Al armoured cable</b> from pole to MDB with all	15	Rmt		
	Rate in words				
7	<b>4core x6sqmm Cu armoured cable</b> MPB to lighting DB <b>4core x6sqmm</b>	3	Rmt		
	Rate in words				
8	<b>3core x 4sqmm PVC insulated Cu wire</b> for UPS I/O <b>3core x 4sqmm PVC</b>	65	Rmt		
	Rate in words				
9	<b>2core x 4sqmm PVC insulated Cu flexible cable</b> for AC <b>2core x 4sqmm</b>	85	Rmt		
	Rate in words				
10	<b>3core x 2.5sqmm PVC Cu armoured cable</b> for outside lighting <b>3core x</b>	7	Rmt		
	Rate in words				
	SITC of light point wiring using 1100V grade with 3 nos. 1.5sqmm Cu PVC insulated wires (Polycab / RR Kable / Finolex) pulled through 20/25mm PVC conduits. All drops from the junction to light point must be in a flexible pipe with glands at junction box including cost of switches, conceal box, plates and required accessories ( Anchor Roma / Wipro )				
11	<b>Primary Light points</b>	40	Nos		
	Rate in words				

12	<b>On board 6A light points</b>	6	Nos		
	Rate in words				
13	on wall <b>Fan points</b> with 6A switch socket on wall <b>Fan points</b> with 6A switch	8	Nos		
	Rate in words				
14	SITC of <b>circuit point wiring</b> using 2 nos. 2.5sqmm + 1no.1.5 sqmm green Cu PVC insulated wires (Polycab / RR Kable / Finolex) pulled through 25mm PVC conduits on wall or partition from MDB to SWBs complete.SITC of <b>circuit point wiring</b> using 2 nos. 2.5sqmm + 1no.1.5 sqmm green Cu PVC insulated	95	Rmt		
	Rate in words				
15	SITC of 5/15A <b>Raw power point</b> using ms concealed box, modular surface plates, modular switches/ sockets and required accessories ( Anchor Roma / Wipro ) SITC of 5/15A <b>Raw power point</b> using ms concealed box, modular	8	No		
	Rate in words				
16	SITC of 6A 3/5 pin <b>3 nos socket and one no. 16A switch Raw power point</b> using ms concealed box, modular surface plates, modular switches/ sockets and required accessories ( Anchor Roma / Wipro ) SITC of 6A 3/5 pin	8	No		
	Rate in words				
17	SITC of <b>6A socket / switch seperate power point</b> using ms concealed box, modular surface plates, modular switches/ sockets and required accessories ( Anchor Roma / Wipro ) SITC of <b>6A socket / switch seperate</b>	15	No		
	Rate in words				
18	SITC of <b>16A switch socket power point</b> using ms concealed box, modular surface plates, modular switches/ sockets and required accessories ( Anchor Roma / Wipro ) SITC of <b>16A switch socket power point</b> using ms	5	No		
	Rate in words				
19	SITC of <b>UPS point wiring</b> using 2 nos. 2.5sqmm + 1 no. 1.5sqmm Cu PVC insulated wires (Polycab / RR Kable / Finolex) complete.SITC of <b>UPS point wiring</b> using 2 nos. 2.5sqmm + 1 no. 1.5sqmm Cu PVC insulated wires (Polycab / RR Kable / Finolex) complete.SITC of <b>UPS point wiring</b> using 2 nos. 2.5sqmm + 1 no. 1.5sqmm Cu PVC insulated wires (Polycab / RR Kable / Finolex) complete.	95	Rmt		
	Rate in words				
20	SITC of <b>Raw point wiring</b> using 2 nos. 2.5sqmm + 1 no. 1.5sqmm Cu PVC insulated wires (Polycab / RR Kable / Finolex) complete.SITC of <b>Raw point wiring</b> using 2 nos. 2.5sqmm + 1 no. 1.5sqmm Cu PVC insulated wires (Polycab / RR Kable / Finolex) complete.SITC of <b>Raw point wiring</b> using 2 nos. 2.5sqmm + 1 no. 1.5sqmm Cu PVC insulated wires (Polycab / RR Kable / Finolex) complete.	95	Rmt		
	Rate in words				
	SITC of light fixtures complete (Wipro/ Phillips) with all fittings like tubes, lamps, etc with required accessories.				
21	P/F <b>LED lighting fixture Wipro Spacio 35W LM15-321-XXX-60-XXP/F LED</b>	13	Nos		
	Rate in words				
22	<b>make 13W P/F LED Wipro/ Panasonic make 13W</b>	22	Nos		
	Rate in words				
23	make 24 WP/F Trim <b>LED TL fitting Wipro make 24 W</b>	4	Nos		
	Rate in words				
24	P/F 48" (1200 mm sweep) @350 to 420 rpm <b>Ceiling fan</b> plain white of Crompton / Bajaj / Anchor / Orient PSPO makeP/F 48" (1200 mm sweep) @350 to 420 rpm <b>Ceiling fan</b> plain white of Crompton / Bajaj / Anchor / Orient PSPO make	1	Nos		
	Rate in words				
25	P/F 16"(40cms) 230V, 50Hz, 3speed <b>Wall fan</b> Crompton/ Usha / Bajaj makeP/F 16"(40cms) 230V, 50Hz, 3speed <b>Wall fan</b> Crompton/ Usha / Bajaj make	1	Nos		
	Rate in words				
26	P/F <b>9W LED</b> bulb Bajaj/Wipro/ Phillips make in toiletP/F <b>9W LED</b> bulb Bajaj/Wipro/ Phillips make in toilet	3	Nos		
	Rate in words				
27	P/F <b>9" Exhaust fan</b> with flaps Bajaj/GEC make in toiletP/F <b>9" Exhaust fan</b> with flaps Bajaj/GEC make in toilet	2	Nos		
	Rate in words				
28	P/F <b>Ding -dong bell</b> with remote completeP/F <b>Ding -dong bell</b> with remote complete	1	No		
	Rate in words				
29	SITC of <b>20 pair telephone tag block</b> with 10 pair module with termination and crimping complete. (Delton make)SITC of <b>20 pair telephone tag block</b> with 10 pair module with termination and crimping complete. (Delton make)	1	No		
	Rate in words				
30	SITC of telephone point with 1 no. <b>RJ11 socket</b> and 1 module plate with box complete. SITC of telephone point with 1 no. <b>RJ11 socket</b> and 1 module plate with box complete.	6	Nos.		
	Rate in words				
31	SITC of <b>2 pair 0.5mm telephone unarmoured cable</b> ( Delton / Finolex ) in 25mm PVC conduit SITC of <b>2 pair 0.5mm telephone unarmoured cable</b> ( Delton / Finolex ) in 25mm PVC conduit	80	Rmt		
	Rate in words				

32	SITC of <b>Earth station</b> as per IS :3049 (Cu plate 600mmx600mm) complete.	2	Nos		
	Rate in words				
33	SITC of <b>10SWG Cu wire</b> in 20mm PVC conduit	75	Rmt		
	Rate in words				
34	SITC of <b>invertor light point</b> wiring using 2 nos. 1.5sqmm Cu wires (Polycab / RR Kabel / Finolex) complete.	85	Rmt		
	Rate in words				
35	SITC DP MCB with metal box with <b>32A DPMCB</b> (Legrand/ Siemens) for AC & satbilizer	10	Nos		
	Rate in words				
	<b>TOTAL AMOUNT FOR ELECTRICAL WORK Rs.</b>				
<b>E</b>	<b>DATA WORK</b>				
1	Labour charges for refixing the existing port patch panel and rack with cable termination and all connections complete.	1	No		
	Rate in words				
2	SITC 2 mt Digilink make patch chord	10	No		
	Rate in words				
3	SITC 1 mt Digilink make patch chord	10	No		
	Rate in words				
4	SITC RJ45 with box / plate / connectors complete set	9	No		
	Rate in words				
5	Supplying and laying of CAT-6 UTP cable of Digilink make in separate conduits/ casing capping complete.	135	Rmt		
	Rate in words				
	<b>TOTAL AMOUNT FOR DATA WORK Rs.</b>				
<b>F</b>	<b>AIR-CONDITIONING WORK</b>				
1	Labour charges including civil work like puncturing the wall and allied cement plaster finishing work for fixing of AC units complete.	5	No		
	Rate in words				
2	SITC EPC bracket stand for outdoor unit	5	No		
	Rate in words				
3	SITC Cu piping with insulation along with 4 core cable with 25mm PVC drain pipe all 3mtr each	5	No		
	Rate in words				
4	SITC 2.0T split unit AC 3star (Carrier/ LG/ Blue star)	4	No		
	Rate in words				
5	SITC 1.5T split unit AC 3star	1	No		
	Rate in words				
6	SITC 5KVA stabilizer	4	No		
	Rate in words				
7	SITC 4KVA stabilizer	1	No		
	Rate in words				
8	SITC additional Cu piping with insulation per Rmt is Rs. 650/- approx.				
	All the above is inclusive of all taxes				
	<b>TOTAL AMOUNT FOR AIR-CONDITIONING WORK Rs.</b>				
	<b>GRAND SUMMARY</b>				
	Civil work				
	Furniture work				
	Chairs				
	Electrical work				
	Data work				
	Air-conditioning work				
	<b>GRAND TOTAL AMOUNT</b>				
	Rates are inclusive of all materials/ taxes/ labour/ octroi/transportation except Service tax				
	Service tax shall be paid seperately				
	Signature of the contractor / Seal of the firm with date.				